



# DAV S.C.B. MEDICAL PUBLIC SCHOOL

AFFILIATED TO C.B.S.E. VIDE AFFILIATION NO.: 1530396 & SCHOOL NO.: 16183

OMP SQUARE, CUTTACK, ODISHA

Ref.No. DAVSCB/CTC/...662/2023.....

Date ...20-10-2023.....

## QUOTATION CALL NOTICE

### QUOTATION FOR INTERIOR FURNISHING WORK

Sealed Quotations are invited by the undersigned from reputed firms/suppliers for INTERIOR FURNISHING WORK. The interested agencies to submit their quotations for the purpose may obtain the prescribed Quotation Form from the office of the undersigned on all working days between 10.00am to 02.00pm from 20.10.2023 to 26.10.2023. The Quotation of the supplier/bidder should be sent in sealed envelope superscribed as QUOTATION FOR for INTERIOR FURNISHING WORK on or before 26.10.2023.


The quotations will be opened in the office of the Principal, DAV S.C.B. Medical Public School OMP Square, Cuttack at 4.30pm on 27.10.2023.

There should not be any overwriting or corrections in the quotations.

The undersigned does not bind himself/herself to accept the lowest quotation and reserves the right to accept the quotation in whole or part.

The quotations received after the stipulated Date & Time or incomplete in any respect shall not be considered. The quotations without GST No. shall not be considered also.

The undersigned reserves the right to cancel any or all the quotation/s without assigning any reason thereof.

  
PRINCIPAL  
PRINCIPAL  
DAV S.C.B. Medical Public School  
Cuttack

Copy to: -

1. The Notice Board & Website of the school for information of all concerned.
2. The Regional Director, DAV Institutions, Odisha for information.
3. The Principal, DAV Public Schools, Bhubaneswar & Cuttack with a request to kindly take steps to display the Quotation Call Notice on the School Notice Board and Websites for information of the public/person concerned.
4. The concerned file for record.

**MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRAGUPTA ROAD, NEW DELHI-55**

**ADDRESS : AT-OMP SQUARE, PO-COLLEGE SQUARE, CUTTACK-753003**

**PH.: 0671-2414245, E-mail : davscbmpps@gmail.com**

DAV S.C.B. MEDICAL PUBLIC SCHOOL, OMP SQUARE, CUTTACK

PHONE NO. 0671-2414245/3510068

Ref. No.: DAVSCB/CTC/...../2023

Date:.....

**QUOTATION FORM FOR INTERIOR FURNISHING WORK**

Name of the Agency: \_\_\_\_\_

Address: \_\_\_\_\_

PAN No. : \_\_\_\_\_ GST: \_\_\_\_\_

Sl. No.	Descriptions	Unit	Rate (per sqft/pc)
1.0	Providing ,fitting & Fixing Wall panneling in the <b>Conference Hall</b> including cost of aluminium frame work along with 9mm thick BWP ply wood & Finishing with 1mm Thick laminate complete in all respect including labour & materials.	Sqft	
2.0	Providing ,Fixing & Fitting <b>Reception Table</b> with 19mm BWR Ply wood and finishing with 1.0mm thick Laminate finishing including hardwire materials & labour complete, in all respect.	Nos	
3.0	Providing ,Fixing & Fitting <b>Executive Table (Principial Table)</b> with 19mm BWR Ply wood and finishing with 4.0mm thick veneer & Malamine polish finishing including hardwire materials & Labour, complete in all respect. <b>Size : 10' x 3'</b>	Nos	
4.0	Providing ,fitting & fixing <b>Storage Cabinet</b> with 19mm thick BWR ply in inner side 0.8mm thick Laminate & the exposed surface fixing 1.00 thcik Laminate & with Hardwire complete in all respect, including Labour & materials.	Sqft	
5.0	Providing ,Fixing & Fitting <b>Executive Table</b> with Side credenza 19mm BWR Ply wood and finishing with 1.0mm thick Laminate Finishing including required hardwire materials & Labour complete in all respect. <b>Size: 5' x 2.6"</b>	Nos	

Sl. No.	Descriptions	Unit	Rate (per sqft/pc)
6.0	Providing and fixing 600 mm wide, 750 mm high and 1200 mm long <b>Work Station for Systems Room</b> fabricated out of 19 mm thick termite and water proof of approved make ply wood finished with 1.0 mm thick laminate on top along with all other exposed surfaces including exposed internal surface top, front, drawers inside, shutter inside, all internal surface & exposed Leg & CPU space to be finished with 1mm th.Laminate complete with set of drawers shelves & shutter as per architectural drawing with wood moulding complete with necessary hardwares, sliding channels, Keyboard drawer, cupboard lock, handles & magnet catcher of any approved make like Godrej or equivalent and all the wooden surfaces finished with French polish including providing and fixing steel cable Manager and making good the surface.	Nos	
7.0	Providing ,Fixing & Fitting <b>Lab. Assistance Table</b> with 19mm BWR Ply wood and finishing with 1.0mm thick Laminate Finishing including required hardwire materials & Labour complete in all respect .Size (4'0" x 2.0")	Nos	
8.0	Providing and fixing in position partly glazed <b>Low Height Partition wall</b> as shown in the architectural drawing including comprising by the frame work of 600 x 600 grid (horizontally and vertically) made up of 50mm x25mm Aluminium section wood Section and / or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour. The rate includes fixing of 12 mm thick glass as per design All exposed Teak wood surfaces to be finished with melamine polish to match the shade of laminate colour including the cost of all materials, labours, hardwares, etc. all complete as per the direction of Engineer-in-charge.	Sqft	
9.0	Providing & Fixing <b>Conference Table of 21 seating capacity</b> with 19mm thick BWR Ply Board with 1mm thick decoartive Laminate & edge fixing 45mm teak beading wth malamine polising including Labour & materials.L 21'4" X W 8'5" X H 2'6"	Nos	
10.0	Providing ,fitting & fixing different lable Gypsum Board Ceiling of <b>Entrance Lobby</b> with required G I chanell & hardwire including labour & materials.	Sqft	
11.0	Providing and Applying two coat plastic emulusion paint, two coat putty and one coat primer including all labour, materials and T&P etc. complete.	Sqft	

Sl. No.	Descriptions	Unit	Rate (per sqft/pc)
<b>ELECTRICAL WORK</b>			
1.0	Supplying ,Fitting & Fixing 15 watt Round LED Light Havles make in lobby area.	Nos	
2.0	2X2.5 + 1X2.5 sqmm FRLS Cupper wire (for Light plug circuit wiring) as required etc. Complete in all respect as per direction of Engineer-in-charge.	Mtr	
3.0	Single light point controlled by one 6A switch or first light point of group control as required etc. Complete in all respect as per direction of Engineer-in-charge.	Nos	
4.0	2nos 4sq mm wire + 1nos of 2.5sq mm + 20mm pvc conduct pipe for <b>AC point</b>	Mtr	
5.0	2X1.5 + 1X1.0 sqmm FRLS Cupper wire (for Light plug circuit wiring) as required etc. Complete as per direction of Engineer-in-charge.( fan point & light point)	Mtr	
6.0	2nos 10A socket + 2nos 10A switch+ 6 Module Plate, <b>Power Point</b> , Administrative Office-12nos,Principal Chamber-4nos, Supervisor-4nos & Conference Hall-1	Mtr	
7.0	1nos of 32Amp DP Indicator Switch with 2Module plate + 1nos of 16Amp Socket with 2Modul plate For <b>AC Point</b>	Nos	
8.0	Supplying ,fitting & Fixing 2ft Fan Down Rod including Labour & materials.	Nos	
<b>N.B.: The transportation Charge included. GST ..... % extra.</b>			
Any other Terms/Conditions:			
1)			
2)			
Please take exact measurement, design & specification before submission of the quotation.			
Signature with seal of the supplier,			
Address & Mobile No.			